

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 09 2006  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Colorado Interstate Gas Company  
Address: P. O. Box 1087, Colorado Springs, CO 80944  
Phone: (719) 520-4557 Operator License #: 7117  
Type of Well: Other - Gas Storage GWI Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: March 16, 2005 (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Keyes Sand Depth to Top: 4,852' Bottom: 4,862' T.D. 5,076'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-129-19001-00-02  
Lease Name: Boehm Gas Storage  
Well Number: Boehm #06  
Spot Location (QQQQ): SE - NW - \_\_\_\_\_ - \_\_\_\_\_  
2,970 Feet from  North /  South Section Line  
2,890 Feet from  East /  West Section Line  
Sec. 10 Twp. 33 S. R. 42  East  West  
County: Morton  
Date Well Completed: 3/27/57  
Plugging Commenced: 1/17/06  
Plugging Completed: 1/18/06

KCC  
3EM  
2-9-06  
RBDMS  
P 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	1,359'	8-5/8"	1,359'	0'
		0'	5,075'	5-1/2"	5,075'	0'
		0'	5,037'	3-1/2"	5,037'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 150# cottonseed hulls ahead of 230 sx Class A Cmt down 3-1/2" casing; pressure tested to 200 psig. Pumped 30 sx Cmt down 5-1/2" X 3-1/2" annulus; pressure tested to 250 psi. Pumped 15 sx Cmt into 8-5/8" X 5-1/2" annulus, pressure tested to 520 psig. Dug out and cut off 4' below ground level.

Welded on proper I. D. plate. Covered pits.

Name of Plugging Contractor: Eagle Well Service, Inc. License #: 7407  
Address: 1661 West 7th Street, Liberal, KS 67901

Name of Party Responsible for Plugging Fees: Colorado Interstate Gas Company

State of Colorado County, El Paso, ss.


Anthony P. Trinko (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Anthony P. Trinko

(Address) 2 N. Nevada Ave., Colorado Springs, CO 80903

SUBSCRIBED and SWORN TO before me this 7th day of February, 2006

Richard Crane My Commission Expires: 7-17-2009  
Notary Public



My Commission Expires 7-17-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Ben