

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

FEB 09 2006

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

Lease Operator: Colorado Interstate Gas Company  
 Address: P. O. Box 1087, Colorado Springs, CO 80944  
 Phone: (719) 520-4557 Operator License #: 7117  
 Type of Well: Other - Gas Storage Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: March 16, 2005 (Date)  
 by: Steve Durrant (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: 1,413' Bottom: 1,860' T.D. 4,952'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-129-20246-00-02  
 Lease Name: Boehm Gas Storage  
 Well Number: Boehm #30  
 Spot Location (QQQQ): NE - SE - \_\_\_\_\_ - \_\_\_\_\_  
2,410' Feet from  North /  South Section Line  
132 Feet from  East /  West Section Line  
 Sec. 10 Twp. 33 S. R. 42  East  West  
 County: Morton  
 Date Well Completed: 10/26/76  
 Plugging Commenced: 1/19/06  
 Plugging Completed: 1/21/06

KCC  
SEM  
2-13-06  
REDM

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	141'	13-3/8"	141'	0'
		141'	1,370'	8-5/8"	1,229'	0'
		0'	75'	9-5/8"	75'	0'
		75'	4,944'	5-1/2"	4,869'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 15# hulls w/125 sx Cmt from 1,900' GL. Tagged TOC @ 1,012' GL. Pumped 80 sx Cmt @ 700' GL; circulated to surface. Pumped 80 sx down 13-3/8" X 9-5/8" annulus and pressure tested to 500 psi. Filled 5-1/2" casing to surface w/10 sx Cmt. Pumped 15 sx down 9-5/8" X 5-1/2" annulus and pressured to 500 psi. Dug out and cut off 4' below ground level. Welded on proper I. D. plate. Covered pits.

Name of Plugging Contractor: Eagle Well Service, Inc. License #: 7407  
 Address: 1661 West 7th Street, Liberal, KS 67901

Name of Party Responsible for Plugging Fees: Colorado Interstate Gas Company  
 State of Colorado County, El Paso, ss.


Anthony P. Trinko (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Anthony P. Trinko

(Address) 2 N. Nevada Ave., Colorado Springs, CO 80903

SUBSCRIBED and SWORN TO before me this 9th day of February, 2006

Richard Crane My Commission Expires: 7-17-2009  
 Notary Public



My Commission Expires 7-17-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEM