

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tengasco, Inc.
Address: PO Box 458 Hays, Ks 67601
Phone: (785) 625-6374 Operator License #: 32278
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1-30-06 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3515 Bottom: 3519 T.D. 3777

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-21,641 ~00-00
Lease Name: Jaco
Well Number: #2
Spot Location (QQQQ): SW - NW - NE -
990 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 13 Twp. 10 S. R. 18 East West
County: Rooks
Date Well Completed: 5-13-82
Plugging Commenced: 1-30-06
Plugging Completed: 1-30-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil & water	0	286'	8-5/8"	4-6-82	
		0	3777	4-1/2"	4-17-82	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tied onto 8-5/8" csg. Mixed & pump 10 sx cmt. Ran tbg to 3340', spotted 80 sx cmt, pulled tbg to 1700 pumped 65 sx to circ cmt.
Pulled tbg, filled 4-1/2" to surface w/ 15 sx. 170 total sx 60/40 pozmix w/ 10% gel & 200# hulls.

Name of Plugging Contractor: Xtreme Well Service License #: 33369
Address: PO Box 244 Ellinwood, Ks 67526
Name of Party Responsible for Plugging Fees: Tengasco, Inc
State of Kansas County, Ellis, ss.
Gary Wagner

RECEIVED
FEB 03 2006
KCC WICHITA


(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Wagner
(Address) PO Box 458 Hays, Ks 67601

SUBSCRIBED and SWORN TO before me this 15th day of Feb, 20 06

Linda K. Pfannenstiel My Commission Expires: 2/5/08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



bm