

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

FEB 10 2006

KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Vincent Oil Corporation  
Address: 125 N. Market, Suite 1075 Wichita, Kansas 67202  
Phone: (316) 262-3573 Operator License #: 5004  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)  
The plugging proposal was approved on: 12-26-05 (Date)  
by: Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Marmaton Depth to Top: 4810 Bottom: 4824 T.D. 4990  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 097-21135 - 00 - 00  
Lease Name: Hiebsch  
Well Number: 2  
Spot Location (QQQQ): E/2 - SW - NE - 32 NE  
1920 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 27 Twp. 29 S. R. 18  East  West  
County: Kiowa  
Date Well Completed: 7-10-85  
Plugging Commenced: 1-30-06  
Plugging Completed: 1-31-06

KCC  
BEM  
2-13-06  
RBDms  
CP 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
as above	oil			8 5/8 in.	518'	0'
				4 1/2 in.	4989'	3180'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4770', dumped 4 sacks, rip at 3280' & 3180', pulled to 1200' and pumped 12 sxs gel and 50 sxs of cement.

Pulled to 530' and pumped 50 sxs of cement, pulled to 40' and pumped 20 sxs of cement.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 400 West Main, Lyons, KS. 67554  
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation  
State of Kansas County, Sedgwick, ss.

Richard A. Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch


(Address) 125 N. Market, Suite 1075 Wichita, Kansas 67202

SUBSCRIBED and SWORN TO before me this 9th day of February

20 06

Yolanda Eubanks  
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bem

# ALLIED CEMENTING CO., INC.

22630

Federal Tax I.D.#

RECEIVED

FEB 10 2006

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT

KCC WICHITA

*Med Lodge*

DATE	1-31-06	SEC	27	TWP	28	RANGE	18	CALLED OUT	1:30	ON LOCATION	3:00pm	JOB START	4:00pm	JOB FINISH	5:30pm
LEASE	Huebsch	WELL #	2	LOCATION	Greenburg	1 E	8 S	COUNTY	Kiowa	STATE	Ks				
OLD OR NEW (Circle one)	<input checked="" type="radio"/> OLD <input type="radio"/> NEW														

CONTRACTOR Paulity Well  
 TYPE OF JOB Plug  
 HOLE SIZE 7 7/8 T.D. 1200  
 CASING SIZE 4 1/2 DEPTH 1200  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX 100 MINIMUM 50  
 MEAS. LINE SHOE JOINT  
 CEMENT LEFT IN CSG.  
 PERFS.  
 DISPLACEMENT 105 bbls water

OWNER Vencent Oil Co.

CEMENT  
 AMOUNT ORDERED 120 sx 60/40/6  
12 sx gel

COMMON	72	A	@	8.70	626.40
POZMIX	48		@	4.70	225.60
GEL	18		@	14.00	252.00
CHLORIDE			@		
ASC			@		
			@		
			@		
			@		
			@		
			@		
			@		
HANDLING	138		@	1.60	220.80
MILEAGE	40 x 138 x .06				331.20
					TOTAL <u>1656.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Mark  
 # 343 HELPER Steve  
 BULK TRUCK  
 # 389 DRIVER Clint  
 BULK TRUCK  
 # DRIVER

REMARKS:

Pump 12 gel + 50 sx at 1200 ft  
Load hole pump 50 sx at 530 ft  
Load hole + pump 20 sx at 40 ft

SERVICE

DEPTH OF JOB 1200  
 PUMP TRUCK CHARGE 100.00