

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD**
K.A.R. 82-3-117

RECEIVED

FEB 10 2006

KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____

API Number: 15 - 039-20959-0000

Lease Name: Bekitombre Unit

Well Number: #1-13

Spot Location (QQQQ): S2 - SW - SE -
90 Feet from North / South Section Line

1900 Feet from East / West Section Line

Sec. 13 Twp. 3 S. R. 27 East West

County: Decatur

Date Well Completed: D&A

Plugging Commenced: 1/28/06

Plugging Completed: 1/29/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	261	8 5/8	261	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Allied Cementing plugged hole as follows with 60/40 Poz, 6% gel, 25 sx @ 2200', 100sx @ 1550', 40 sx @ 300', 10 sx @ 40', 15 sx in rathole, 10 sx in mousehole. Started at 9:15 pm (1/28/06) and completed at 12:00 am (1/29/06).

Ordered by Case Morris with KCC/Hays.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.


State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



and SWORN TO before me this 8th day of February, 20 06

Susan Brady My Commission Expires: 11-4-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bon