

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION

OIL & GAS CONSERVATION DIVISION FEB 10 2006

WELL PLUGGING RECORD

K.A.R. 82-3-117

RECEIVED

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 10/06/05 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

4247-49, 4213-15, 4205-10, Depth to Top: Bottom: T.D.

4182-84, 4164-69, 4084-87, Depth to Top: Bottom: T.D.

4024-32, 4008-4013 Depth to Top: Bottom: T.D.

API Number: 15-153-20498-00-02

Lease Name: Texaco Cahoj Unit

Well Number: #902

Spot Location (QQQQ): NW - NE - NW - 320 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 9 Twp. 1 S. R. 34 East West

County: Rawlins

Date Well Completed: 2/84

Plugging Commenced: 1/23/06

Plugging Completed: 1/23/06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surface and Production data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Rig up Swift Services. Pumped 115 sx SMD cement & 400# hulls, no circulation. Pulled tubing to 1200'. Pumped 75 sx SMD & 300# hulls, no circulation. Pulled tubing to 600'. Pumped 60 sx SMD & 200# hulls & circulated cement to surface. TOH w/tbg. Pumped 15 sx down 8 5/8". SI @ 300#. Hooked onto 5 1/2". Pumped 60 sx SMD cement & 100# hulls. Max press 800#. SI @ 0#. Let sit 15 min, csg full. Total cement 325 sx. Witnessed by Darrel Dipman w/KCC. Job complete @ 2:30 pm.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300; Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



Subscribed and SWORN TO before me this 8th day of February, 2006

Susan Brady My Commission Expires: 11-4-07 Notary Public

[Handwritten mark]