

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 09 2006
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Colorado Interstate Gas Company
Address: P. O. Box 1087, Colorado Springs, CO 80944
Phone: (719) 520-4557 Operator License #: 7117
Type of Well: Other - Gas Storage GWT Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: March 16, 2005 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
'G' Sand Depth to Top: 4,740' Bottom: 4,762' T.D. 5,005'

API Number: 15-129-20146-00-01
Lease Name: Boehm Gas Storage
Well Number: Boehm #17
NENE
Spot Location (QQQQ): SE - NE - - -
3,880' Feet from North / South Section Line
132 Feet from East / West Section Line
Sec. 15 Twp. 33 S. R. 42 East West
County: Morton
Date Well Completed: 10/24/74
Plugging Commenced: 12/16/05
Plugging Completed: 12/22/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	137'	13-3/8"	137'	0'
		137'	1,376'	8-5/8"	1,239'	0'
		0'	81'	9-5/8"	81'	0'
		81'	4,998'	5-1/2"	4,917'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 4,700' GL. Set 20 sx Cmt on top of CIBP. Tagged TOC @ 4,100' GL. Pumped 30 sx Cmt @ 1,400' GL. Pumped 90 sx Cmt @ 750' GL.
Top of Cmt at surface. Pumped 10 sx Cmt down 13-3/8" X 9-5/8" annulus and pressured to 500 psi. Cut off, weld ID plate. Clean up location.


Name of Plugging Contractor: Eagle Well Service, Inc. License #: 7407
Address: 1661 West 7th Street, Liberal, KS 67901

Name of Party Responsible for Plugging Fees: Colorado Interstate Gas Company
State of Colorado County, El Paso, ss.

Anthony P. Trinko (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) 2 N. Nevada Ave., Colorado Springs, CO 80903

SUBSCRIBED and SWORN TO before me this 7th day of February, 2006
Richard Crane My Commission Expires: 7-17-2009
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

My Commission Expires 7-17-2009

Ben