

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 09 2006
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled
CONSERVATION DIVISION
WICHITA, KS

Lease Operator: Colorado Interstate Gas Company
Address: P. O. Box 1087, Colorado Springs, CO 80944
Phone: (719) 520-4557 Operator License #: 7117
Type of Well: Other - Gas Storage Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: November 10, 2005 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Keyes - Gas Storage Depth to Top: 4,842' Bottom: 4,868' T.D. 5,987'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 129-10266-00-01
Lease Name: Boehm Gas Storage
Well Number: Boehm #01
Spot Location (QQQQ): NE NE - NW -
4,950 Feet from North / South Section Line
3,030 Feet from East / West Section Line
Sec. 14 Twp. 33 S. R. 42 East West
County: Morton
Date Well Completed: 07/09/1952
Plugging Commenced: 12/29/05
Plugging Completed: 1/11/06 - 1-6-06 *KCC AB 2-2006*

*KCC
AB
2-2006
RBD/ms
CP 2/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	260'	13"	260'	0'
		0'	2,711'	8-5/8"	2,711'	740'
		0'	5,030'	5-1/2"	5,030'	2,036'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 4,757' GL. Spotted 20 sx Cmt plug on CIBP. Tagged TOC @ 4,360' GL. Pumped 30 sx Cmt plug @ 2,750' GL. Pumped 65 sx Cmt plug in 8-5/8" @ 2,027' GL.

Spotted 60 sx plug @ 715' GL. Spotted 75 sx plug @ 450' GL. Pumped 30 sx from 60' to surf. Cut off & capped 4' below ground and welded proper I. D. plate.

Covered Pits.

Name of Plugging Contractor: Eagle Well Service, Inc. License #: 7407
Address: 1661 West 7th Street, Liberal, KS 67901

Name of Party Responsible for Plugging Fees: Colorado Interstate Gas Company

State of Colorado County, Ellis, ss.


Anthony P. Trinko (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 2 N. Nevada Ave., Colorado Springs, CO 80903

SUBSCRIBED and SWORN TO before me this 7th day of February, 2006

[Signature] My Commission Expires: 7-17-2009
Notary Public



My Commission Expires 7-17-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Am