

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078  
Wichita, Kansas 67202

RECEIVED  
FEB 6 2006

KCC WICHITA

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-175-22028-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation KCC LICENSE # 5142  
(owner/company name) (operator's)

ADDRESS: 8080 E. Central, Suite 300 CITY: Wichita

STATE: Kansas ZIP CODE: 7278-020867206 CONTACT PHONE: 316-636-2737

LEASE: Grant 'A' WELL#: 1-5 Section 5 Township 31s Range 31w

N/2 Ne Nw SPOT LOCATION/QQQQ COUNTY: Seward

330 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_  
CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 1852' KB CEMENTED WITH 600 SACKS  
PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 2824 G.L. 2833 K.B. T.D. 5560 PBTD \_\_\_\_\_ Anhydrite Depth 1735  
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:  
Plugging orders received from Eric Maclaren on 01/28/06. Bottom plug at 3350' w/ 100 sx;  
2nd plug at 1880' w/ 50 sx; 3rd plug at 600' w/ 50 sx; Top plug at 60' w/ 20 sx. All plugs  
60/40 Poz, 6% Gel. Plugged rathole with 15 sk, mousehole 10sx. Job complete 6:15 pm  
on 01/28/06. Acid Services ticket # 10381. Sterling reported plugging to KCC on 01/30/06.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes \_\_\_\_\_ (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: W. C. "Bill" Craig/Gary M. Talbott Phone#: (620) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142  
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (if Known?) Plugged well at 6:15 pm on January 28, 2006. *Plugged*

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent \_\_\_\_\_

DATE: 01/28/06 AUTHORIZED OPERATOR OR AGENT: Gary M Talbott  
(signature) Gary M. Talbott, Agent for Operator

# Sterling Drilling Company, Rig #2

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

RECEIVED  
FEB 16 2006

KCC WICHITA

## SAMPLE LOG

Grant 'A' 1-5

**LOCATION:** N/2 Ne Nw Section 5 T 31s R 31w  
**API:** 15-175-22028-00-00 Seward County, Kansas

**OWNER:** McCoy Petroleum Corporation  
**CONTRACTOR:** Sterling Drilling Company, Rig #2

**COMMENCED:** 01/17/06  
**COMPLETED:** 01/28/06

**TOTAL DEPTH:** **DRILLER** 5560 FEET  
**LOGGER** 5548 FEET

**Ground Elevation:** 2824  
**KB Elevation:** 2835

## LOG

0 -	2 FEET	Top Soil
2 -	600 FEET	Surface Sands and Clay
600 -	1735 FEET	Clays, Sandstone and Shales
1735 -	1752 FEET	Anhydrite (Driller's)
1752 -	2620 FEET	Clays, Sandstone, Shales & Salt
2620 -	5560 FEET	Limestone/Shales

## CASING RECORDS

### Surface Casing:

Spud at 7:15 pm on 01/17/06. Drilled 12-1/4" hole to 1858'. Ran 46 joints of new 24# 8-5/8" surface casing tally 1840.32' set at 1852' KB. Welded straps on bottom 3 and top joints. Tacked collars on remainder. Cemented w/ 475 sx A-Con; 3% CC & 1/4# Cellflake/sx and 125 sx Class A w/ 2% C.C; 1/4 #/sx Celloflake. Cement did circulate. Plug down at 9:15 pm on 01/19/06. Acid Services ticket #10378.

### Production Casing:

Plugging orders received from Eric Maclaren on 01/28/06. Bottom plug at 3350' w/ 100 sx; 2nd plug at 1880' w/ 50 sx; 3rd plug at 600' w/ 50 sx; Top plug at 60' w/ 20 sx. All plugs 60/40 Poz, 6% Gel. Plugged rathole with 15 sk, mousehole 10sx. Job complete 6:15 pm on 01/28/06. Acid Services ticket # 10381. Sterling reported plugging to KCC on 01/30/06.

## DEVIATION SURVEYS

1 degree(s) at	1383	feet
3/4 degree(s) at	1858	feet
3/4 degree(s) at	4068	feet
1 degree(s) at	5560	feet