

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

RECEIVED  
FEB 06 2006

KCC WICHITA

API #: 15-007-22966-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation KCC LICENSE # 5003  
(owner/company name) (operator's)

ADDRESS: 8080 E. Central, Ste 300 CITY: Wichita

STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737

LEASE: Landis Trust WELL#: A 1-21 Section 21 Township 32s Range 10w

Se Se Ne SPOT LOCATION/QQQQ COUNTY: Barber

2310 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_  
CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 222' KB CEMENTED WITH 225 SACKS  
PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 1454 G.L. 1463 K.B. T.D. 4820 ~~4500~~ 4500 STD KCCap 2-20-06 Anhydrite Depth ???  
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:  
Plugging orders received from Eric Maclaren on 01/27/06. Bottom plug at 600' w/ 50 sx;  
2nd plug at 250' w/ 40 sx; Top plug at 60' w/ 20 sx. Used 135 sx 60/40 Poz, 6% Gel.  
Plugged rathole with 15 sk, mousehole 10sx. Job complete 12:30 pm on 01/28/06.  
Acid Services ticket # 11913. Sterling reported plugging to KCC on 01/30/06.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes \_\_\_\_\_ (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lanny Saloga/Gary M. Talbott Phone#: (620) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142

(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 12:30 pm on January 28, 2006. Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent \_\_\_\_\_

DATE: 01/28/06 AUTHORIZED OPERATOR OR AGENT: Gary M Talbott

(signature) Gary M. Talbott, Agent for Operator

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

RECEIVED  
FEB 06 2006

KCC WICHITA

## SAMPLE LOG

## Landis Trust A 1-21

LOCATION: Se Se Ne  
API: 15-007-22966-0000

Section 21 T 32s R 10w  
Barber County, Kansas

OWNER: McCoy Petroleum Corporation  
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 01/19/06  
COMPLETED: 01/28/06

TOTAL DEPTH: DRILLER 4820 FEET  
LOGGER 4824 FEET

Ground Elevation: 1454  
KB Elevation: 1463

## LOG

0 -	3 FEET	Top Soil
3 -	12 FEET	Sand & Gravel
12 -	38 FEET	Clay
38 -	60 FEET	Sand & Gravel
60 -	1660 FEET	Shales and Salt
1660 -	4820 FEET	Limestone/Shales

## CASING RECORDS

### Surface Casing:

Spud at 2:15 pm on 01/19/06. Drilled 12-1/4" hole to 225'. Ran 5 jts. of new 23# 8-5/8" surface casing tallied 210.74' set at 221.74' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC & 1/4 # per sx Celloflake. Plug down at 9:15 pm on 01/19/06. Cement did circulate. Acid Services ticket # 11804. Welded straps on bottom 2 joints, welded collars on 3 joints.

### Plugging Data:

Plugging orders received from Eric Maclaren on 01/27/06. Bottom plug at 600' w/ 50 sx; 2nd plug at 250' w/ 40 sx; Top plug at 60' w/ 20 sx. Used 135 sx 60/40 Poz, 6% Gel. Plugged rathole with 15 sk, mousehole 10sx. Job complete 12:30 pm on 01/28/06. Acid Services ticket # 11913. Sterling reported plugging to KCC on 01/30/06.

## DEVIATION SURVEYS

3/4 degree(s) at 225 feet  
3/4 degree(s) at 4450 feet