

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-26706-00-00
Spot: N2SEW Sec/Twnshp/Rge: 11-32S-9E
1650 feet from N Section Line, 1980 feet from W Section Line
Lease Name: VOIGTLANDER A Well #: 6
County: CHAUTAUQUA Total Vertical Depth: 2246 feet

Operator License No.: 31119
Op Name: WOLFE, ROBERT & DEBBIE S.
Address: BOX 241
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40	0	

#73⁰⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/04/2006 9:00 PM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: ROB WOLFE Company: LONE WOLF OIL CO. Phone: (620) 647-3626

Proposed Plugging Method: TO PUMP CEMENT THROUGH DRILL PIPE FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: NONE
Date/Time Plugging Completed: 01/04/2006 11:50 PM KCC Agent: RON ROWE

Actual Plugging Report:

Perfs:

PUMPED 15 SACKS CEMENT THROUGH DRILL PIPE FOR BOTTOM PLUG @ 2246'. PULLED PIPE TO 1500' & PUMPED 15 SACKS CEMENT. PULLED DRILL PIPE TO 450' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED DRILL PIPE & TOPPED-OFF WELL. PUMPED 15 SACKS CEMENT IN RAT-HOLE. USED TOTAL OF 145 SACKS CEMENT & 10 SACKS GEL.

RECEIVED
KCC DISTRICT #3

JAN 31 2006

CHANUTE, KS

RR

RECEIVED
FEB 6 2006
KCC WICHITA

Remarks: PLUGGED NEWLY DRILLED DRY HOLE.

Plugged through: DP

District: 03

Signed

[Signature]
(TECHNICIAN)

INVOICED

DATE

2-7-06

INV. NO

2006061083