

3 023009

15-001-27954-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-040
NE,NW,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
4938 feet from south section line
1826 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101 100

Lease/Well# JONES 13
County ALLEN

Operator: STATE OF KANSAS Fee Fund
Name & (FEE FUND PLUGGING)

Well Total Depth 800' feet
Production Pipe: 2 7/8" Size Feet 800'
Surface Casing: 6 1/4" Size Feet 20'

Address _____
AB oil well X Gas Well _____ SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670
Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: _____ Month: 26 _____ 1 2006

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. EVIDENTLY THE WELL CONTAINED
1" PIPE FROM T.D. TO 130'. IT DID NOT TO PROVE POSSIBLE TO REMOVE THE 1".
THE PLUGGING PROPOSAL WAS TO FILL AS MUCH OF THE WELL AS POSSIBLE FULL
OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All X Part _____ TECHNICIAN
None _____

Operations Completed: Hour: 2:30P.M. Day: _____ Month: 26 _____ 1 2006

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 130'.
CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE
2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. THE 1" PIPE WAS REMOVED.
THE PUMPE TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. CEMENT
WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE.
THE WELL WAS THEN SHUT IN AT 350P.S.I.. 30 SACKS OF CEMENT WERE PUMPED
INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.3.) (API NO. 15-001-27,954.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
FEB 08 2005
KCC WICHITA

Bum