

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03026-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 3-9S-19W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ROSTOCIL Well #: 4
County: ROOKS Total Vertical Depth: 3489 feet

Operator License No.: 0
Op Name: LANDOWNER
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	3480	0	w/unknown sxs cmt
SURF	10.75	211	0	w/unknown sxs cmt

113³⁹

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/05/2006 1:00 PM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEAVERLING Company: ROME CORPORATION DBA WEST Phone: (785) 625-1118

Proposed Plugging Method: Note: Mr. Robert Rostocil owns this well personally and hired Western Well Service, a licensed well plugging contractor, to plug this well.
Ordered 250 sxs Swift Multi-Density Cement and 800# hulls.
Ran wireline. PBTB 3210'. Fluid level 400'. PBTB 3465'.
No squeeze records - Perf: salt - anhy. - Base Dakota.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2006 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 1875' - 1525' - 725'.
Ran tubing to 3200'. Swift Services pumped 95 sxs Swift Multi-Density Cement with 300# hulls.
Pulled tubing to 1580'. Swift Services pumped 90 sxs SMD with 300# hulls.
PTOH. Squeezed 15 sxs SMD.
Max. P.S.I. 400#. S.I.P. 400#.
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3434	3444		
3416	3428		

RECEIVED
FEB 6 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 2-7-06
INV. NO. 2006061082

Form CP-2/3

JAN 19 2006

CONTINENTAL OIL COMPANY

#4 ROSTOCIL

3-9-19W
NW SW SE

Contr.

ROOKS

Coun

E 2059

Comm

Comp

3-2-51

IP

83 BOPD

PHY POT

Tops	Depth	Datum
HEEB	3192	-1133
DODGE	3213	-1154
LANS	3232	-1173
ARB	3479	-1420
T.D.	3489	-1430

Casing

10" 211
6" 3480

ACID 500: DD 3489
 1/2 BOPH: ACID 1000
 1/2 BOPH: ACID 3000
 60 BO/24 HRS: PB 3460
 CO 3481: WTR: SQZ
 DD 3489: ACID 500
 5 GO & 1 BWPH
 PB 3466: PERF 3434-44,
 3416-28: ACID 1000
 1 BOPH/14 HRS: ACID
 NOVOTNY POOL 2000: 1/2 BOPH/24
 HRS: ACID 500: SWB 50
 BO/24 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS