

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-09428-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 3-9S-19W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ROSTOCIL Well #: 5  
County: ROOKS Total Vertical Depth: 3530 feet

Operator License No.: 0  
Op Name: LANDOWNER  
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3529	0	w/200 sxs cmt
SURF	10.75	254	0	w/225 sxs cmt

\$114.<sup>73</sup>

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/06/2006 2:30 PM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: AVEN WEAVERLING Company: ROME CORPORATION DBA WEST Phone: (785) 625-1118

Proposed Plugging Method: Note: Mr. Robert Rostocil owns this well personally and hired Western Well Service, a licensed well plugging contractor, to plug this well.  
Ordered 450 sxs 60/40 pozmix - 10% gel - 1000# hulls.  
Ran wireline in hole - bridge at 720'. Fluid at 10'.  
No squeezed records. Perf: 1875' - 1525' - 725'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/09/2006 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

01/06/2006  
Ran notch collar and tubing to 720'. Fell thru bridge at 720'.  
Ran tubing to 2000'. Pulled tubing out, perforated 1875' - 1525' - 725'.  
Ran tubing to 3150'. Allied pumped 200 sxs 60/40 pozzmix - 10% gel with 400# hulls.  
Pulled to 1800'. Allied pumped 100 sxs cement with 400# hulls.  
Pulled to 800'. Allied pumped 120 sxs cement with 100# hulls.  
Hooked up to backside and pumped 40 sxs cement with 100# hulls.  
Max. P.S.I. 200#. S.I.P. 200#.  
01/09/2006  
Ran tubing and tagged cement at 620'.  
Allied pumped 50 sxs cwc.  
PTOH. Topped off with cement.

RECEIVED  
FEB 6 2006

KCC WICHITA

RECEIVED  
FEB 6 2006

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 2-7-06  
INV. NO. 2006061082

Form CP-2/3

JAN 25 2006

CONTINENTAL OIL

#5 RCSTOIL

3-9-19W

SW SW SE

Contr.

ROOKS


County

E 2076 KB Comm. 12/11/62 Comp. 1/10/63

IP 60 BOPD + 20 BW/  
LANS 3240-3446

LOG Tops	Depth	Datum
TOP	2991	- 915
HEEB	3194	-1118
LANS	3241	-1165
ARB	3488	-1412
TD	3530	-1454

Casing 45 BOPD + 15 BW  
10" 254/225 TOP 3144-317  
7" 3529/200 SX: PERF (LANS)-  
8/3390-94, 16/3240-48, 14/3257-64, 6/3275-78,  
6/3295-97, 8/3380-84, 10/3401-06, 4/3418-20,  
12/3432-46: ACID 500 GAL, SWB 1 BO + 10 GAL  
WPH/2HRS: ACID 500 GAL; SWB 1/2 BO + 2 BAWPH/2HRS;  
ACID 1000 GAS, SWB 1/2 BO + BAWPH/2 HRS: ACID  
500 GAL, SWB, NO OIL, 3/4 BAWPH/2 HRS: ACID  
1500 GAL, SWB 2 BO + 1 1/4 BAWPH/2 HRS: SWB 4 1/2 BO +  
4 BAWPH/3 HRS FROM ALL ZONES:  
PERF (TOP) 20/3144-51; A2000G, SWB 8 BO + 10  
BSWPH/3 HRS: PERF 14/3166-73; A 2000 C;  
BARRY 6 BO + 4 BAWPH/2 HRS: REA 1000 GAL,  
SWB 6 BO + 3 BAWPH/2 HRS, REA  
1000 GAL, SWB 10 BO + 2 BAWPH/  
2HRS: SWB ALL PERF, TSTD 19  
BO + 5 BAWPH/3 HRS:



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

PERF (ARB) 16/3492-3500; SWB ; NO OIL, 10 BAWPH/3 HRS:  
SET PERM BRIDGE PKR 3473: SET MODEL D PKR 3226: