

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20959-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 13-3S-27W  
90 feet from S Section Line, 1900 feet from E Section Line  
Lease Name: BEKITOMBRE Well #: 1-13  
County: DECATUR Total Vertical Depth: 3850 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	261		

# 12513

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2006 11:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEITH Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 01/29/2006 12:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st. Plug at 2200' w/25 sxs.  
2nd. Plug at 1550' w/100 sxs.  
3rd. Plug at 300' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)



**INVOICED**

DATE 2-10-06  
INV. NO. 200601095

RECEIVED

FEB 10 2006

KCC WICHITA

Form CP-2/3

FEB 02 2006