

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-42268-00-00
Spot: SENESW Sec/Twnshp/Rge: 15-29S-1W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: O S A UNIT Well #: 19
County: SEDGWICK Total Vertical Depth: 3800 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: PO BOX 729 - 102 S. RIVER ROAD
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3799		200 SX CMT
SURF	8.625	320		300 SX CMT

#123⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2006 10:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 438-2856

Proposed Plugging Method: Perfs 3751' - 3757'; sand to 3700' & 5 xs; and circ from 370' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/19/2006 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 3700' and capped with 6 sacks of cement. The casing was recovered from 1720' and pulled from the wellbore. Tubing was ran to 370' where cement was circulated to surface.

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3751	3757		


RECEIVED
KCC DISTRICT #2
FEB - 3 2006
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed



RECEIVED
FEB 08 2006
KCC WICHITA

INVOICED
(TECHNICAL)
DATE 2-8-06
INV. NO 2006061089