

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21831-00-01

Spot: S2SW

Sec/Twnshp/Rge: 17-15S-25W

660 feet from S Section Line,

1420 feet from W Section Line

Lease Name: DEINES OWWO

Well #: 1

County: TREGO

Total Vertical Depth: 2247 feet

Operator License No.: 30420

Op Name: INNONE, VINCENT DBA V.J.I. NATURA

Address: 30-38 48TH STREET

ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	247		

#73⁰³

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/31/2006 12:00 PM

Plug Co. License No.: 33724

Plug Co. Name: WARREN DRILLING, LLC

Proposal Rcvd. from: GILBERT SMITH

Company: WARREN DRILLING, LLC

Phone: (620) 665-6088

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES

WitnessType: NONE

Date/Time Plugging Completed: 01/31/2006 2:30 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

1st. Plug at 1190' w/25 sxs.
2nd. Plug at 882' w/100 sxs.
3rd. Plug at 298' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ACID SERVICES, INC.

Plugged through: DP

District: 04

Signed

Roger A. Moses

(TECHNICIAN)

RECEIVED

FEB 08 2006

KCC WICHITA

INVOICED

DATE

2-8-06

INV. NO

2006061088


Form CP-2/3

FEB 03 2006

INDEXED

REPLACEMENT CARD

JOHN JAY DARRAH, JR. 17-15-25W
 412 E. DOUGLAS, #1 #1 DEINES 100'E.
 WICHITA, KS. 67202 C S/2 SW
 CONTR MALLARD DRILLING CTY TREGO
 GEOL BETH FUHR FIELD WC 1/4 NW OF
 SPLITTER, OVER 1/2
 MI FROM PROD)
 ELV 2435 KB SPD 12/15/85 CARD ISSUED 4/10/86 IP D&A/MISS
 2427 GL DRLG COMP 12/23/85 12/23/85
 API 15-195-21.831



SMP	Tops	Depth/Datum	
			8 5/8" 247.10 / 155 SX NO CORES
ANH	1880+	555	DST (1) 3970-4025 (LKC) / 30-30-30-30, REC 75' M, NSO, SIP
HEEB	3722	1287	1196-1024#, FP 33-44#
LANS	3762	1327	DST (2) 4272-4380 (MARM, CHER, MISS) / 30-30-45-45, REC
BKC	4056	1621	420' MCO (APPX 54% M, 41% OIL, 4% G, 1% W), SIP 1034-
PAW	4192	1757	948#, FP 121-230#
FT SC	4260	1825	
CHER SH	4286	1851	
CHER SD	4340	1905	
MISS	4377	1942	
RTD	4450	2015	
NO LOG			

INFO RELEASED: 4/30/87 - WAS D & A - TIGHT HOLE

NOTE: CORRECTION: 1/7/86 - ORIGINALLY FIRST REPORTED AS
 860' FSL & 1370' FWL, SW/4

COPYRIGHT 1987
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS