

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-183-20017-00-00
Spot: SWNW Sec/Twnshp/Rge: 36-2S-15W
1980 feet from N Section Line, 660 feet from W Section Line
Lease Name: ARMENT Well #: 1
County: SMITH Total Vertical Depth: 4300 feet

Operator License No.: 33687
Op Name: SALT CREEK EXPLORATION, INC.
Address: PO BOX 998
BRANSON, MO 65616

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	253		

#139⁷⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/09/2006 11:00 AM
Plug Co. License No.: 33724 Plug Co. Name: WARREN DRILLING, LLC
Proposal Rcvd. from: GILBERT SMITH Company: WARREN DRILLING, LLC Phone: (620) 933-2040

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 02/09/2006 12:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1875' w/25 sxs.
2nd. Plug at 1025' w/100 sxs.
3rd. Plug at 305' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED
FEB 15 2006
KCC WICHITA

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 2-15-06
INV NO 2006061125

Form CP-2/3

FEB 13 2006