

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24179-00-00
Spot: SENESW Sec/Twnshp/Rge: 8-14S-19W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RIEDEL Well #: 3
County: ELLIS Total Vertical Depth: 3950 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3948	0	w/175 sxs cmt
SURF	8.625	211	0	w/135 sxs cmt

#12838

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2006 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: _____ Company: DUANE ACHTERBERG Phone: (785) 628-3834

Proposed Plugging Method: Order 300 sxs 60/40 pozmix - 10% gel.
8 5/8" at 211' w/135 sxs cmt. 5 1/2" at 3948' w/175 sxs cmt.
DV at 1560' w/350 sxs cmt.
Solid bridge at 889' - took injection rate - 2 bbls a minute at 300# P.S.I.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2006 12:15 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Ran TIH to 887' - pumped 90 sxs 60/40 pozmix - 10% gel cement - circulated.
Pulled 1" tubing and tied onto 5 1/2" casing - pumped 210 sxs 60/40 pozmix - 10% gel.
Max. P.S.I. 500#. S.I.P.200#.
Tied onto 8 5/8" & 5 1/2" annulus - immediate 300# P.S.I. (Backside full).

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

RECEIVED
FEB 15 2006
KCC WICHITA

District: 04

Signed Ed Schumacher
(TECHNICIAN)

INVOICED

DATE 2-15-06

INV. NO 2006061122

Form CP-2/3

FEB 14 2006

replacement card

WEILERT ENTERPRISES
HAYS KS

8-14S-19W
SE NE SW

#3 RIEDEL

site: 4-1/4 S & 1-1/4 W OF YOCEMENTO KS

city: ELLIS

API 15-051-24179

contr: R & C DRILLING

field: KRAUS

opdr: DAN NIXON

fr date 03/05/85

spdr date 03/13/85

drig comp 03/20/85

card issued 02/20/86

last revised 07/26/89

ELV: 2208 KB, 2203 GL LOG	
tops.....	depth/datum
ANH.....	1478 + 730
B/ANH.....	1523 + 685
TOP.....	3197 - 989
HEEB.....	3463 - 1255
TOR.....	3486 - 1278
LANS.....	3505 - 1297
BKC.....	3771 - 1563
CONG CHT.....	3810 - 1602
CONG SD.....	3856 - 1648
B/CONG SD.....	3863 - 1655
ARB DOL.....	3945 - 1737
LTD.....	3950 - 1742
RTD.....	3950 - 1742

IP status:

OIL, P 10 BO & 20 BWP, LKC 3530-3714 OA, ARB
3948-3950, 05/08/85
CORR & INFO REL: 7/26/89 - CORR IP; WAS OIL WELL
- TIGHT HOLE
NOTE: CORR 3/28/85 - ORIG FR IN SE SE SW
CSG: 8-5/8" 211 / 135 SX (ALT 2), 5-1/2" 3948 / 175 SX,
DV TOOL AT 1560 / 350 SX
DRLR SD ZNS: 30-945 (SD & SH), 945-1168, 1345-1478
(SH & SD), 1523-2065 (SH & SD)
NO CORES OR DSTS

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

WEILERT ENTERPRISES
HAYS KS

8-14S-19W
SE NE SW

#3 RIEDEL

MICT - CO, (ARB OH), SO, NAT, PF (KC) 16/24/3701-3707, 3710-3714, AC 1500 GAL (15% REG),
SWB LD, SO, RE-AC 3000 GAL (28% REG), SO, PF (KC) 24/3680-3686, AC 1500 GAL (15% REG),
SO, PF (KC) 24/3654-3660, AC 2000 GAL (28% REG), SO, PF (LANS) 24/3530-3536, AC 1500 GAL
(15% REG), SO, SET 2-3/8" TBG AT 3863, NO PKR, POP; IPP 10 BO & 20 BWP, NSG,
COMMINGLED, DOFP 5/8/85