

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-20853-00-00  
Spot: NENESW Sec/Twnshp/Rge: 2-26S-4E  
2179 feet from S Section Line, 2674 feet from E Section Line  
Lease Name: PAULSON A Well #: 98  
County: BUTLER Total Vertical Depth: 2445 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2108	0	225 SX CMT
SURF	8.625	231	0	150 SX CMT

# 79 46

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2006 10:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: 25 sxs @ 1650'; 15 sxs @ 450'; circ from 280' to surf.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/27/2006 4:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Spotted 35 sacks of Class A cement at 1654'. Tagged plug at 1440'. RIH with tubing at 480'.  
Spotted 15 sacks of Class A cement. Tagged cement at 690'. RIH with tubing at 480'. Spotted  
15 sacks of Class A cement. Tagged cement at 1419'. Set bridge plug at 300'. Perforated 5-  
1/2" casing at 278' - 279'. Established circulation. United Cementing mixed and pumped 150  
sacks of 60/40 posmix with 4% gel to surface.

United Cement #6756

Perfs:

Top	Bot	Thru	Comments
1981	1988		
1960	1968		
1652	1673		

RECEIVED  
KCC DISTRICT #2  
FEB - 3 2006  
WICHITA, KS

RECEIVED  
FEB 14 2006  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

*Duane R. Krueger*

(TECHNICIAN)

INVOICED

DATE 2-14-06  
VOL. NO. 2006061111