

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-22636-00-00

Spot: SENESENE

Sec/Twnshp/Rge: 5-24S-17E

3563 feet from S Section Line, 271 feet from E Section Line

Lease Name: KUNKEL

Well #: 2

County: WOODSON

Total Vertical Depth: 1212 feet

Operator License No.: 30102

Op Name: CHRIESTENSON, ROBERT

Address: PO BOX 41
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1212	0	
SURF	7	40	0	

39 38

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/03/2006 9:30 AM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: ROBERT CHRISTENSON

Company: ROBERT CHRISTENSON

Phone: (620) 963-2342

Proposed
Plugging
Method:

THIS WELL CONSISTED OF 2 7/8" CASING TO 1212' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/03/2006 10:00 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1000P.S.I.. 40 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

FEB 8 2006 CPT

CHANUTE, KS

RECEIVED
FEB 13 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

INVOICED
DATE 2-13-06
INV NO 2006061102