

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22467-00-00  
Spot: W2SWSE Sec/Twnshp/Rge: 35-34S-38W  
660 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: K U ENDOWMENT C Well #: 4  
County: STEVENS Total Vertical Depth: 7010 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY  
Address: 13727 NOEL RD., STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6312		WITH 2 SX CMT
CIBP		6675		
PROD	5.5	6995	2480	WITH 275 SX CMT
SURF	8.625	1759		WITH 580 SX CMT

# 227<sup>83</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2006 9:00 AM  
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE  
Proposal Rcvd. from: DAVID Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: CIBP @ 6300' WITH 2 SX CMT. PLUG AT 1780' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/27/2006 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 6312' WITH 2 SX CMT. 1ST PLUG AT 2475' WITH 30 SX CMT. 2ND PLUG AT 1800' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
6844	6896		
6362	6408		

RECEIVED  
FEB 15 2006  
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE.

Plugged through: TBG

District: 01



Signed

Jim Holland PART II  
(TECHNICIAN)

INVOICED

DATE 2-15-06  
# 200606121