



15-179-20194-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 14 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 4-14-69

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. John Kohlrus of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Kohlrus guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company,

Complete Address: 520 Cameron Bldg., Oklahoma City, Oklahoma.

Lease Name: Cooper Well No. 1

Location: NE-NE-NE Sec. 1 Twp. 7 Rge. (E)(W) 26

County: Sheridan Total Depth 3900 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Kohlrus was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent