

State of Kansas



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 Feb 12, 1968 FEB 12 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg Co., Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: Box # 797, Great Bend, Kansas.

Lease Name: Moore Well No. B-2

Location: NW-NW Sec. 36 Twp. 7 Rge. (E)(W) 25

County: Graham Total Depth 3975 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burris was instructed to plug the well as follows:

212'--8 5/8" Surface pipe, cement circulated with 160 Sx.

Circulate hole with heavy mud. Pull DP to 1220' and displace 100 Sx.

cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

*M. L. Dehala*  
 Conservation Division Agent