

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1972 MAR 10, 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerry Nestlerode of Chief Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Nestlerode guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company., Incorporated,

Complete Address: 905 Centruy Plaza, Wichita, Kansas.

Lease Name: H. Moore Well No. B-3

Location: CN/2-NE-NW Sec. 36 Twp. 7 Rge. (E)(W) 25

County: Graham Total Depth 3994' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nestlerode was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent