



15-179-20172-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water) 212 N. Market  
 500 Insurance Bldg. WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 20 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

1-20-69

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Bangle Well No. 1

Location: CE/2-E/2-NW/4 Sec. 5 Twp. 7 Rge. (E)(W) 26

County: Sheridan Total Depth 4060' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

282'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1275'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx. cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent