



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
01-15-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. George Klein of Messman-Rinehart Oil Co., has this date requested permission to plug the following described well:

Mr. Klein guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company,

Complete Address: 1432 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Hatfield Well No. 1

Location: CW/2-NW-NW Sec. 22 Twp. 7 Rge. (E)(W) 29

County: Sheridan Total Depth 4230 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Klein was instructed to plug the well as follows:

349'--8 5/8" Surface casing, cement circulated with 280 Sx.  
Top of Dakota section @ 1325'.

Circulate hole with heavy mud. Pull DP to 1550' and displace 100 Sx.  
cement thru DP. Pull DP to 375' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*A. L. Nichols*  
Conservation Division Agent