



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-179-202 50-00-00

RECEIVED
STATE CORPORATION COMMISSION
05-10-1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Csg. Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Hummon Oil, Incorporated,

Complete Address: 821 Union National Building, Wichita, Kansas.

Lease Name: Pope Well No. 1

Location: SW-NW-NE Sec. 19 Twp. 7 Rge. (E)(W) 29

County: Sheridan Total Depth 4249' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

287'--8 5/8" Surface casing, cement circulated.
4249'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4150'. Top perforations from 4070' to 4078'.

Push plug to 4060', sand back to 4050' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 135 Sx. cement, staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent