

State of Kansas



15-179-20079-00-00

# State Corporation Commission

## CONSERVATION DIVISION

WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 25 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 03-25-1968

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Cyril Denning of Dean & Clark, Incorporated has this date requested permission to plug the following described well:

Mr. Denning guarantees payment of the plugging fee.

Operator's full Name: Dean & Clark, Incorporated,

Complete Address: 416 Union Center Building, Wichita, Kansas.

Lease Name: Hezterberg Well No. 1

Location: CNE-NE-NE Sec. 25 Twp. 7 Rge. (E)(W) 29

County Sheridan Total Depth 4220 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Denning was instructed to plug the well as follows:

288'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Top of Dakota @ 1700'.

Circulate hole with heavy mud. Pull DP to 1920' and displace 100 Sx.  
thru DP. Pull DP to 300' and displace 20 Sx. cement thru DP. Pull DP,  
set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent