



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-179-20283-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas

05-24-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Frank Neff of Nadel & Gussman has this date requested permission to plug the following described well:

Mr. Neff guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman,

Complete Address: 514 Union Center Building, Wichita, Kansas.

Lease Name: Teel Well No. 1

Location: CSE-SE Sec. 18 Twp. 7 Rge. (E)(W) 30

County: Sheridan Total Depth 4220' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Neff was instructed to plug the well as follows:

325'-- 8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 100 Sx.
cement thru DP. Pull DP to 340' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent