

15-065-03085-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Well Drilled 1959 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil and Gas Corp. OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400
1980' FSL

LEASE (FARM) Fabricius U. WELL NO. 302W WELL LOCATION 660' FEL COUNTY GRAHAM

SEC. 26 TWP. 7S RGE. 23 ☒ OR ☒ TOTAL DEPTH 3755' PLUG BACK TO 3728'

Check One:

OIL WELL ☐ GAS WELL ☐ D & A ☐ SWD or INJ. WELL INJ. DOCKET NO. E-11084

SURFACE CASING SIZE 8-5/8" SET AT 226' CEMENTED WITH 165 SACKS

CASING SIZE 5-1/2" SET AT 3755' CEMENTED WITH 125 SACKS

PERFORATED AT 3692-98', 3702-06'

CONDITION OF WELL: GOOD ☐ POOR ☒ CASING LEAK ☐ JUNK IN HOLE ☐

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL KCC field approved plugging procedure is attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES
IS ACO-1 FILED? Completed 1959 (If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Unknown at this time.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J.D. Hininger Phone # (913) 674-2182

ADDRESS Cities Service Oil and Gas Corp., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Halliburton Oil Services

LICENSE NO. 613

ADDRESS Oberlin, KS 67749

PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hill 3/4/88

(Operator or Agent)

DATE: 3-3-88

①



CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

Wichita, Kansas

15-065-03085-00-01

TO: Mr. M. D. Harrison
FROM: Mr. Phil W. Pringle

SUBJECT: PLUGGING PROCEDURE.....FABRICIUS UNIT 302W
LOCATION 1980' ECL - 660' FEL
SEC 26 TWP 7S RGE 23W
GRAHAM COUNTY, KANSAS

WELL DATA:

SURFACE CSG. 8 5/8" O 226' W 165 SX
PRODUCTION CSG. 5 1/2" O 3755' W 125 SX
PERFORATIONS 3692-98', 3702-06'
PBT D 3728' TD _____
CASING CONDITION POOR

SHALLOW FORMATION DATA:

DAKOTA 805-930'
CHEYENNE 1010-1185'
ANHYDRITE 1215-50'

KCC FIELD APPROVAL BY MR. DENNIS HAMEL (11/16/87)

- 1) Prior to plugging, contact Mr. Hamel at the District office #4, Hays, Kansas, phone number (913) 628-1200.
- 2) Perforate above the Anhydrite at 1205' with 4 SPF, perforate below the Dakota at 980' with 3 SPF, and perforate below the surface casing at 231' with 3 SPF.
- 3) Tie onto the 5-1/2" casing and fill the long pipe & casing annulus to surface with cement, Hulls and Flocele. (Approx. 300 sx cement, 6 sx Hulls and 75 # Flocele.
- 4) Let cement sit 48 hours, check top of cement and cap well. Note: cement calculations based on 65/35 cement with 10% gel + 2% econolite additive. Slurry volume 3.62 Ft³/sx, blend ratio 23 gals. water/sx. Add 1/4# Flocele/sx slurry.

cc: J. D. Hininger (2)
Andrew McCalmont
Allen D. Grubb
File

State of Kansas



15-065-03085-00-01

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

March 7, 1988

JUL 7 '88

WELL PLUGGING NOTICE

EXPIRES

Fabricius U #302W (Inj.)
1980' FSL 660' FEL
Sec. 26-07S-23W
Graham County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112


Gentlemen: . .

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,


Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200