

15-065-01308-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
500 INSURANCE BUILDING  
212 NORTH MARKET  
WICHITA, KANSAS 67202

FORM CP-1

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

1/13/69

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Specter Pipe & Supply, Inc.

Address Russell, Kansas

Lease (Farm Name) Wanker "A" Well No. 1

Well Location C <sup>SE</sup> NE Sec. 35 Twp. 7 Rge. 23 (E) (W) W

County Graham Field Name (If Any) \_\_\_\_\_

Total Depth 3765 Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Well Log filed with application Yes or Well Log filed with Plugging Supervisor \_\_\_\_\_

Date and hour plugging is desired to begin Immediately

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of company representative in charge of plugging operations Lynch Casing Pulling Company

Address R.R. 4, Gt. Bend, Kansas

Plugging Contractor Lynch Casing Pulling Co. License No. \_\_\_\_\_

Address R.R. 4, Gt. Bend, Kansas

Invoice covering assessment for plugging this well should be sent to Specter Pipe & Supply, Inc.

Address P.O. Box 169, Russell, Kansas

and payment will be guaranteed by applicant.

Signed: [Signature]  
Applicant or Acting Agent

Date: Jan. 11, 1969

State of Kansas



15-065-01308-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

January 13, 1969

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Wanker "A"
Description	C SW NE 35-7-23W
County	Graham
Total Depth	3765
Plugging Contractor	Lynch Casing Pulling Co.

Specter Pipe & Supply, Inc.  
 P. O. Box 169  
 Russell, Kansas 67665

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

*J. Lewis Brock*  
 J. Lewis Brock, Administrator

Mr. W. L. Nichols Box 157 Morland, Kansas  
 is hereby assigned to supervise the plugging of the above named well.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

**COPY**

15-065-01308-00-00


Company- **IMPERIAL OIL OF KANSAS, INC.**  
 Farm- **Wanker** No. 1

SEC. 35 T. 7  
 C SE NE

R. 23W

Total Depth. 3765'  
 Comm. 10-24-58 Comp. 11-3-58  
 Shot or Treated.  
 Contractor. Imperial Oil of Kans., Inc.  
 Issued. 2-7-59

County **Graham**  
 KANSAS



**CASING:**  
 8 5/8" 230' cem w/175 sx.  
 5 1/2" 3765' cem w/125 sx.

Elevation. 2302' RB

Production. 280 BOPD

Figures Indicate Bottom of Formations.

shale & rock	230
shale & sand	1500
Dakota sand	1710
shale & shells	1940
Anhydrite	1975
shale & shells	2825
shale & lime	3537
lime	3765 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Heebner	3516	3517
Toronto	3539	3541
Lansing	3556	3558

**DRILL STEM TESTS:**

- #1 3577-93, op 2 hrs., rec. 930' slightly oil cut salt water, ICIP 1670#, BHP 1290#.
- #2 3595-3615, op 2 hrs., rec. 660' gas, 540' oil, BHP 1200#.
- #3 3620-30, op 1 hr., rec. 450' muddy salt water, BHP 1080#.
- #4 3666-95, op 1 hr., rec. 20' mud, BHP 90#.
- #5 3697-3765, op 1 hr., rec. 25' mud, BHP 300#.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 13 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

1/13/69