


15-065-00809-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County. Sec. 23 Twp. 7S Rge. 23W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Trexler "C" Well No. 2

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 30 19 59

Application for plugging filed April 30 19 59

Application for plugging approved April 30 19 59

Plugging commenced April 30 19 59

Plugging completed April 30 19 59

Reason for abandonment of well or producing formation No Commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius

Producing formation Depth to top Bottom Total Depth of Well 3735 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 220' | 220' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set No. 1 Plug at 550' with 25 sacks cement; Set No. 2 Plug at 220' with 15 sacks cement; Set No. 3 Plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1959

CONSERVATION DIVISION
Wichita, Kansas

8/4/59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Raymond L. Bacon (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P

780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August 19 59

My commission expires July 7, 1962

Mona L. Latier
Mona L. Latier Notary Public.

PLUGGING
FILE SEC. 23 T. 7 R. 23 W.
BOOK PAGE 54 LINE 44

15-065-00809-00-00

DRILLER'S LOG

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1959

CONSERVATION DIVISION
Wichita, Kansas

8/4/59

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Trexler "C" No. 2
C SE NE Sec. 23-7S-23W
Graham County, Kansas

Total Depth: 3735'

Elevation: 2305' R.B.
Production: D & A

Commenced: 4-23-59 Completed: 4-30-59

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 220' with 160 sacks cement.

Figures indicate bottom of formations:

| | | <u>TOPS</u> | |
|---------------------|-------|--------------------|-----------------|
| Surface Clay & Sand | 220' | | |
| Shale | 500' | Anhydrite | 1940' (/ 365) |
| Shale & Sand | 1315' | Heebner | 3524' (-1219) |
| Shale & Dakota Sand | 1940' | Toronto | 3548' (-1243) |
| Anhydrite | 1980' | Lansing | 3565' (-1260) |
| Shale & Shells | 2670' | Rotary Total Depth | 3735' (-1430) |
| Lime & Shale | 3495' | | |
| Lime | 3735' | | |
| Total Depth | 3735' | | |

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *A. Brown*
Vice-President

Subscribed and sworn to before me this 6th day of May, 1959.

My Commission Expires:

July 7, 1962

Mona L. Latier
Mona L. Latier - Notary Public

PLUGGING
FILE SEC. 23 T. 7 R. 23W
BOOK PAGE 55 LINE 44