

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

15-179-20126-00-00

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 27 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 08-27-1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Roy Cook of Imperial Oil Company, has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: Box #784, Great Bend, Kansas.

Lease Name: Hueftle Well No. 1

Location: CNE-NW Sec. 28 Twp. 70 Rge. (E)(W) 30

County: Sheridan Total Depth 4290 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

280'--8 5/8" Surface casing, cement circulated with 200 Sx.

Circulate hole with heavy mud. Pull DP to 1650' and displace 100 Sx. cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent