



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
09-04-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20130-00-00

Dear Sir:

Mr. Roy Cook of Imperial Oil Company, has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Gilchrist Well No. 1

Location: CNEONE Sec. 21 Twp. 7 Rge. (E)(W) 30

County: Sheridan Total Depth 4225 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

3 1/8" --- 8 5/8" Surface pipe, cement circulated with 275 Sx.  
Top of Dakota section @ 1500'.

Circulate hole with heavy mud. Pull DP to 1710' and displace 100 Sx.  
cement thru DP. Pull DP to 420' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent