



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

15-179-20197-00-00

Dear Sir:

Mr. Maynard Weber of Leo J. Dreiling Oil Company, has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Dreiling and Hiko Bell Mining and Oil Company,

Complete Address: R. R. #2, Victoria, Kansas,

Lease Name: Gilchrist Well No. 1

Location: SW-SW-NW Sec. 21 Twp. 7 Rge. (E)(W) 30

County: Sheridan Total Depth 4280' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Weber was instructed to plug the well as follows:

345'--8 5/8" Surface casing, cement circulated.  
4279'--4 1/2" Production casing cemented on bottom with 175 Sx. Well plugged back to 4246'. Top perforations from 4046' to 4048'.

Push plug to 4000' and set 3 sacks cement with dump bailer. Shoot 4 1/2" casing and pull to 1720' and pump in 18 sacks gel then pull 4 1/2" to 1600' and displace 100 Sx. cement. Pull 4 1/2" to 365' and displace 25 Sx. cement Pull 4 1/2" and 10 Sx. cement to bottom of cellar.

RECEIVED

STATE CORPORATION COMMISSION

JUL 1 1969

CONSERVATION DIVISION  
 Wichita, Kansas

07-01-1969

Very truly yours,

Conservation Division Agent