



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-179-20218 -00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 14 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
08-14-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: Box #797. Great Bend, Kansas.

Lease Name: Yelek Well No. 1

Location: CSW-NW Sec. 27 Twp. 7 Rge. (E)(W) 30

County: Sheridan Total Depth 4300' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

326'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1475'.

Circulate hole with heavy mud. Pull DP to 1700' and displace 100 Sx.  
cement thru DP. Pull DP to 335' and displace 20 Sx, cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx, cement to bottom  
of cellar.

Very truly yours,

H. B. Nichols  
Conservation Division Agent