

15-179-20171-00-00

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 7 1969
 JAN 7 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Duane Born of Paine Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company and J. S. Kantor,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Schwarzenberger Well No. 1

Location: App.-SE-SE,-NE Sec. 31 Twp. 7 Rge. (E)(W) 26

County: Sheridan Total Depth 4034 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

220'--7" OD Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 65 Sx.
cement thru DP. Pull DP to 245' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent