

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1969 JAN 5, 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. George Starbuck of Phoenix Drilling Corporation has this date requested permission to plug the following described well:

Mr. Starbuck guarantees payment of the plugging fee.

Operator's full Name: Phoenix Drilling Corporation,

Complete Address: Suite 20, 400 North Woodlawn, Wichita, Kansas.

Lease Name: Sumner Well No. 7

Location: CSW-NW Sec. 28 Twp. 7 Rge. (E)(W) 27

County: Sheridan Total Depth 4135' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Starbuck was instructed to plug the well as follows:

218'--8 5/8" surface casing, cement circulated.
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1470' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent