

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1972
JAN 24 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated.

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Sniffin Well No. 1

Location: CNE-SW-NW Sec. 2 Twp. 7 Rge. (E)(W) 27

County: Sheridan Total Depth 4082' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

249'--8 5/8" Surface casing, cement circulated with 175 Sx. (6 3/4" Hole).
Top of Dakota section @ 1225'.

Circulate hole with heavy mud. Pull DP to 1450' and displace 50 Cu. Ft. cement thru DP. Pull DP to 280' and displace 25 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. G. Nichols
Conservation Division Agent