

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Inc., has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Leidig Well No. 1

Location: SW-SW-NW Sec. 1 Twp. 7 Rge. (E)(W) 27

County Sheridan Total Depth 4085' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

286'--8 5/8" Surface pipe, cement circulated with 150 Sx. Dakota section from 1875' to 1695'.

Run DP. to 1895', circulate hole with heavy mud and displace 100 Sx. cement thru DP. Pull DP. to 300' and displace

20 Sx. cement thru DP. Pull DP. set plug @ 40' with 1/2 sack hulls and 10 Sx. cement into cellar.

Very truly yours,

A. L. Nichol

Conservation Division Agent

JUL 21 1967
JUL 21, 1967
CONSERVATION DIVISION
Wichita, Kansas