

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
AUG 23 1967  
AUG 23, 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 4th Nat'l Bank Bldg., Wichita, Kans.,

Lease Name: Barnett Well No. 1

Location: SE-SE-SE Sec. 24 Twp. 7 Rge. (E)(W) 26

County Sheridan Total Depth 3980' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

267' -- 8 5/8" Surface pipe, cement circulated with 200 Sx. Dakota section from 1800' to 2000'.

Circulate hole with heavy mud. Pull DP to 2020' and displace 100 Sx. cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*A. L. Nichols*  
Conservation Division Agent