

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 18 1967

JUL 18 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drlg. Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Burch Exploration, Incorporated,

Complete Address: 601 Union Center, Wichita, Kansas.

Lease Name: Sheetz Well No. 1

Location: SE-NW Sec. 35 Twp. 7 Rge. (E)(W) 26

County Sheridan Total Depth 3980' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

253' -- 7" OD Surface pipe, cement circulated with 125 Sx. (6 1/4" hole).  
Dakota section from 800' to 985'. Displace 50 Sx. cement thru DP.  
from 1015' to 700'. Pull DP. to 240' and displace 15 Sx. cement  
thru DP. Pull DP. Set plug @ 40' with 1/2 sack hulls and 8 Sx.  
cement to bottom of cellar.

Very truly yours,

Conservation Division Agent