

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sam Farmer of John O. Farmer, Inc., has this date requested permission to plug the following described well:

Mr. Farmer guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Newland Well No. 1

Location: NW-NW-SW Sec. 30 Twp. 7 Rge. (E)(W) 27

County Sheridan Total Depth 4160 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Farmer was instructed to plug the well as follows:

252'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1300'.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx. cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. B. Dechals  
Conservation Division Agent