

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 26 1968 NOV 26
 CONSERVATION DIVISION 1968
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Gerritzen of Rains & Williamson Oil Company has this date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: City of Hoxie Well No. 1

Location: SW-SE Sec. 32 Twp. 7 Rge. (E)(W) 27

County: Sheridan Total Depth 4163 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

283'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1300'.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 20 Sx. cement thru DP.
Pull DP, set bridge : 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
 Conservation Division Agent