

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

15-163-20480-00-00

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER N/A (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR S & M Oil Co. OPERATOR'S LICENSE NO. 8735

ADDRESS 205 N. Jefferson; Plainville, KS PHONE # (913) 434-2829

LEASE (FARM) N. Chesney D WELL NO. 2 WELL LOCATION SE SE NE COUNTY Rooks

SEC. 18 TWP. 8-S RGE. 16-W (E) or (W) TOTAL DEPTH 3150 PLUG BACK TD 3130

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 1129 CEMENTED WITH N/A SACKS

CASING SIZE 5 1/2 SET AT 3140 CEMENTED WITH 150 SACKS

PERFORATED AT 2942 - 3126

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off perforations and cap sand with 5 sacks

cement. Cut off 5 1/2" casing at 1725' & cement 8 5/8 with 225 sacks of 65/35

pos., 10% gel, 1/4 lb. floseal per sack and 1 sack hulls.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? N/A

(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8-13-90 9 am

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Steve Crawford RECEIVED CORPORATION COMMISSION

PHONE # (913) 434-2829 AUG 15 1990

ADDRESS 205 N. Jefferson; Plainville, KS 67663 8-15-90 CONSERVATION DIVISION Wichita, Kansas

PLUGGING CONTRACTOR Allied Cementing LICENSE NO. N/A

ADDRESS Russell, KS PHONE # (913) 483-2627

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Steve Crawford
(Operator or Agent)

DATE: 8-13-90