

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-20,254

LEASE NAME Griffin "B"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. 2110 office within 30 days.

990 Ft. from S Section Line

1320 Ft. from E Section Line

LEASE OPERATOR Shields Oil Producers, Inc.

SEC. 30 TWP. 8 RGE. 15 (E) or (W)

ADDRESS Shields Bldg., Russell, KS. 67665

COUNTY Osborne

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Date Well Completed 10-1-90

Character of Well D & A

Plugging Commenced 10-1-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-1-90

The plugging proposal was approved on 10-1-90 (date)

by Brucy Basye (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,425'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	224'	Cmtd. w/145 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Fill hole w/heavy mud. Push bridge plug to 1,245', spot 20 sax on plug thru drill pipe.
Push bridge plug to 820', spot 100 sax cement on plug thru drill pipe. Push bridge plug
to 275', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax
cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164

Address Shields Bldg., Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 90

Ruth Phillips

Notary Public

My Commission Expires:

