

WELL PLUGGING RECORD 15-141-20164-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Osborne SEC. 30 TWP. 8 RGE. 15 E/W
 Location as in quarters or footage from lines:
SE/SW/SE

Lease Owner Shield Oil Producers
 Lease Name Griffin "A" Well No. #1
 Office Address Shields Bldg. - Russell, Kansas 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced August 1, 1983
 Plugging completed August 9, 1983

Locate Well
 correctly on above
 Section Platt.

Reason for abandonment of well or producing formation _____
Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dale Balthazor
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3472'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	271'	NONE
				4 1/2"	3466'	2495.90'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped five (5) sacks cement on bottom, sanded to 2890' and dumped
 five (5) sacks cement.
 Shot casing at 2650' and 2500'.
 Pulled fifty-nine (59) joints 4 1/2" casing.
 Squeezed well with five (5) sacks hulls, fifteen (15) sacks gel,
 seventy (70) sacks cement, five (5) sacks gel, released plug and pumped
 seventy (70) sacks 50/50 pozmix cement with 4% added gel and 3%
 calcium chloride. Maximum pressure was 400 psi and shutin 200 psi.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD / Box 698 - Great Bend,
 (Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1983



My Commission expires _____

Margaret Prosser
 Notary Public.
 RECEIVED

AUG 11 1983

5-11-83