

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-01122-00-01  
API NUMBER N/A

LEASE NAME Chesney A

WELL NUMBER 2

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 18 TWP. 8S RGE. 16 (X) or (W)

COUNTY Rooks

Date Well Completed 1-9-62

Plugging Commenced 6-19-90

Plugging Completed 6-19-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR S & M Oil Co.

ADDRESS 205 N. Jefferson; Plainville, KS 67663

PHONE#(913) 434-2829 OPERATORS LICENSE NO. 8735

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-19-90 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? N/A - sent in with CP-1 form

Producing Formation LKC Depth to Top 2746 Bottom 3166 T.D. 3220

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	ss, ls, sh	226	surf	8 5/8	226	0
LKC	water	3220	surf	4 1/2	3220	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set.  
Perf at 1180 & base dakota 650. (three holes each). Sq casing 350 to surf. Ordered 50 sks common w/ 1/4 lb f.c. plus 250 sks 65/35 poz 8% gel s/ 1/4 lb. f.c. R.I.H. w/ tubing to 1245; spot 50 sks common w/ 1/4 lb f.c. Pull tubing to 845; spot 50 sks 65/35 poz 8% gel w/ 1/4 lb f.c. Pull tubing to 445; circ cement to surf. w/100 sks  
(If additional description is necessary, use BACK of this form.) (on back)

Name of Plugging Contractor Allied License No. N/A

Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: S & M Oil Co.

STATE OF Kansas COUNTY OF Rooks, ss.

Steve Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Crawford

(Address) 205 N. Jefferson; Plainville, KS

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 90



Connie Newell  
Notary Public

Commission Expires: 4-9-94

w/ $\frac{1}{4}$  lb f.c. and 100 lbs hulls. Pulled tubing; Hooked up to  $4\frac{1}{2}$   
and sq 25 sks 65/35 poz 8% gel and 1 sk hulls: Max 600 lbs.  
s.i. 300 lbs.

