

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

REGISTRATION RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23304-
LEASE NAME Chesney 00-00
WELL NUMBER H-1
2310 Ft. from S Section Line
330 Ft. from E Section Line
SEC. 7 TWP. 85 RGE. 16W (E) or (W)
COUNTY Rooks
Date Well Completed N/A
Plugging Commenced 3-22-99
Plugging Completed 3-26-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Horizontal Development & production Inc,
ADDRESS P.O. Box 12728
PHONE 214-363-8332 OPERATORS LICENSE NO. 30730
Character of Well Oil

(Oil Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on 3-18-99 (date)
by Hays District (Herb Deines) (KCC District Agent's Name).

Is AGO-1 filed? yes If not, is well log attached? N/A
Producing Formation Arb - KC Depth to Top 2964 Bottom 3265 T.D. 3365

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|-------------|------|----|--------|--------|------------|
| | Surface | | | 8"ø | 203 | 0 |
| | Prod string | | | 5 1/2" | 3325 | |
| | | | | 5 1/2" | | 2221 |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Sanded to 2900 Bailed 5 sks cement. Shot 2221' Pulled to 1240'. Pumped 3 hulls & 85 sks. Pulled to 780'. Pumped 1 hull & 40 sks. Pulled to 250'. Pumped 40 sks. Pulled the rest of the pipe. Hole stayed full.


Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 249 Beth Drive Sterling Ks 67579-9048

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Horizontal Development & production Inc
STATE OF _____ COUNTY OF _____, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
APR - 6 1999
SUBSCRIBED AND SWORN TO before me this 5 day of April, 1999

(Signature) David Funks
(Address) 203 S Franklin Russell Ks
Sylvia Newton
Notary Public



CONSERVATION DIVISION
Wichita, Kansas
My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM